



NOTES: FRAME & GRATE

1. SEE CONSTRUCTION DRAWINGS FOR PIPE SIZE, LOCATION AND INVERT ELEVATION.
2. FRAME & GRATE SHALL BE ASTM A-36 STEEL, HOT-DIPPED GALV. AFTER CONSTRUCTION.
3. ALL CONCRETE TO BE 3000 PSI AT 28 DAYS.

LAST REVISION DATE:	COPYRIGHT 1996 WESTECH ENGINEERING, INC.
JANUARY 1998	
TYPE 3 DITCH INLET CATCH BASIN	
CITY: JUNCTION CITY, OR	DRAWING NO. 313